
 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

## Table of Contents

Purpose.....	2
1. Responsibilities.....	2
2. Scope/Applicability.....	2
3. Procedure Detail.....	2
3.1. Monitoring & Analysis Tools.....	2
3.2. Identifying SOL and IROL Exceedances.....	3
3.3. TOP Notification Requirements for SOL Exceedances.....	5
3.4. Actual Thermal SOL Exceedances.....	6
3.5. Actual Voltage SOL Exceedances.....	7
3.6. Actual Stability SOL Exceedances.....	9
3.6.1. RC Validation of Stability Limits Impacting Multiple TOPs.....	9
<b>3.6.2. Stability Limit Versus TTC.....</b>	<b>10</b>
3.6.3. RC Actions to Mitigate Stability Limit Exceedance.....	11
3.7. RTCA Post-Contingency Thermal SOL Exceedances.....	12
3.8. RTCA Post-Contingency Voltage SOL Exceedances.....	14
3.9. IROL Exceedances.....	16
3.10. Insecure Operating State.....	17
3.11. Unsolved Contingencies in RTCA.....	19
3.12. Islanding Conditions.....	20
3.13. Post-Contingency Mitigation Plans.....	20
3.14. Change of RAS Status.....	21
4. Supporting Information.....	21
Operationally Affected Parties.....	21
References.....	22
Definitions.....	22
Version History.....	25
5. Periodic Review Procedure.....	26
Review Criteria & Incorporation of Changes.....	26
Frequency.....	26
Appendix A: RC Exceedance Mitigation Steps.....	27

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

## Purpose

Provide guidance on mitigating System Operating Limits (SOL) and Interconnection Reliability Operating Limits (IROL) exceedances within the Reliability Coordinator (RC) Area. This procedure also outlines tools used to perform the RC function, as well as mitigation options for resolving reliability issues affecting the Bulk Electric System (BES) in a timely manner.

## 1. Responsibilities

- Reliability Coordinator Operator

## 2. Scope/Applicability

- Reliability Coordination

## 3. Procedure Detail


### 3.1. Monitoring & Analysis Tools

This section provides a brief description of the Real-time monitoring and analysis tools RC West utilizes to perform RC functions for the RC Area. These tools are used for monitoring of all BES facilities, the status of Remedial Action Schemes (RAS), and non-BES facilities that impact the BES within the RC Area. RC West monitors facilities within its RC Area and neighboring RC Areas, and makes use of analysis tools to perform Real-time Assessments in order to identify facilities approaching SOL and IROL limits; and to identify SOL and IROL exceedances within the RC West Area.<sup>1</sup> If any of the listed real-time applications or tools fail, the RC operator ensures Real-Time Assessments are performed in a timely manner.<sup>2</sup>

- Energy Management System (EMS)/Supervisory Control and Data Acquisition (SCADA) System**: Provides the RC operator with real-time monitoring and visibility of the status of BES transmission and generation facilities, RAS, non-BES facilities that impact the BES, and other critical real-time parameters for the reliable operation of the BES. The EMS system also provides alarming of critical events that affect the reliability of the BES.
- Real-time State Estimator (RTSE)**: This application performs numerical analysis of the real-time network model and data to determine the system's current condition. The RTSE can typically identify bad analog telemetry, estimate non-telemetered flows and voltages, and determine real-time operating limit exceedances. The RTSE runs every 5 minutes, and provides a base case solution used by RTCA and RT-VSA applications.

<sup>1</sup> IRO-002-7 R5

<sup>2</sup> See RC0520 Loss of Monitoring and Analysis Tools.

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	


- **Real-time Contingency Analysis (RTCA)**: This is a primary Real-time Assessment application that runs every 5 minutes and automatically performs analyses of all identified single and credible multiple Contingencies that affect the RC Area.<sup>3</sup> The RC operator utilizes the results to identify potential post-Contingency thermal or voltage exceedances on the system and to proactively develop mitigation plans to ensure reliability.
- **Real-time Voltage-Stability Analysis (RT-VSA)**: This application runs every 5 minutes and performs voltage-stability analyses of pre-determined stability limitations on the system to determine voltage-stability limits and margins for those interfaces.
- **Real-time Dynamic Stability Analysis (RT-DSA)**: This application runs every 15 minutes and performs transient stability analyses of pre-determined stability limitations on the system to identify transient-stability limits and margins for those interfaces.
- **Plant Information (PI) System**: This is a reliability tool used to process and provide visualization of complex real-time power system information in a user-friendly format for the RC operator to process and analyze. The tool provides real-time trending of power system parameters, which enhances situational awareness.
- **Dispatcher Load Flow (DLF) and Contingency Analysis (CA) Study Tools**: These applications are used by the RC operator to manually run load flow and Contingency analysis studies. The Real-time base case solution from RTSE can be loaded into these applications to be used as a starting point to run analysis of any scenario the operator wants to study.

### 3.2. Identifying SOL and IROL Exceedances

SOLs and IROLs used in Real-time are based on the RC West SOL Methodology (*RC0610: SOL Methodology for the Operations Horizon*), to ensure acceptable system performance pre- and post-Contingency. Operating Plans are documented in procedures, outage cards, next day studies and current day studies, and those limits are programmed into Real-time monitoring and analysis tools to aid the RC Operator in quickly determining if an SOL or IROL is being approached or exceeded.

---

<sup>3</sup> IRO-008-3 R4


 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

When an SOL or IROL exceedance is identified, the RC Operator will work with and compare results with the responsible TOP(s). In instances where there is disagreement in results between entities, the RC Operator will take a conservative approach and operate to the most limiting results.<sup>4</sup>

Reliability Coordinator Actions <sup>5</sup>	
<ul style="list-style-type: none"> <li> <b>Monitor</b> Real-time flows, voltages and status of RAS's on BES and non-BES facilities that impact the BES using the EMS alarms, SCADA, PI, and RTSE to determine any of the following <i>SOL Exceedance</i> conditions: <ol style="list-style-type: none"> <li><u>Actual Thermal SOL Exceedance</u> – Real-time flows exceeding the normal (continuous) rating for a monitored facility and for a duration exceeding the time duration of available Emergency Ratings.</li> <li><u>Actual Voltage SOL Exceedance</u> – Real-time bus voltages are outside the normal (continuous) voltage limits for a monitored facility and for longer than the default time duration of 30 minutes (unless the TOP provides a different time duration for the emergency System Voltage Limit).</li> <li><u>Actual TOP Stability SOL Exceedance</u> – Real-time flows on an interface/path are exceeding a pre-determined stability limit.</li> </ol> </li> <li> <b>Evaluate results</b> from RTCA, RT-VSA, DLF, and CA Study tools to determine any of the following <i>SOL exceedance</i> conditions: <ol style="list-style-type: none"> <li><u>Post-Contingency Thermal SOL Exceedance</u> – Validated Contingency analysis results indicate post-Contingency flows will exceed the highest Emergency (Short-Term) Rating for a monitored facility.</li> <li><u>Post-Contingency Voltage SOL Exceedance</u> – Validated Contingency analysis results indicate post-Contingency bus voltage will be outside the Emergency (Short-Term) limits.</li> <li><u>Insecure Operating State</u> – Single or credible multiple Contingency will result in instability, cascading or uncontrolled separation.</li> </ol> </li> <li> <b>Evaluate results</b> from EMS, PI, RTCA, RT-VSA, DLF, and CA Study tools to determine any of the following <i>IROL exceedance</i> conditions: <ol style="list-style-type: none"> <li><u>IROL Exceedance</u> - Single or credible multiple Contingency will result in exceeding a pre-determined IROL limit.</li> </ol> </li> </ul>	

<sup>4</sup> IRO-009-2 R4, TOP-001-6 R18 (applicable to TOP)

<sup>5</sup> IRO-002-7 R5

	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	


Reliability Coordinator Actions <sup>5</sup>
<ul style="list-style-type: none"> <li>• <b>Evaluate</b> results from PI, RT-VSA, and RT-DSA tools to determine SOL exceedance of a Stability Path impacting multiple TOPs: <ol style="list-style-type: none"> <li>1. <u>Actual RC Stability SOL Exceedance</u> - Real-time flows are exceeding the RC validated active limit for a stability path/interface pre-established as impacting multiple TOPs. The RC SOL Methodology requires that the RC <b>validates</b> stability limits impacting multiple TOPs. <i>RC0310A Stability SOLs and Areas with Risk of Localized Voltage Collapse</i> includes a listing of stability limits that impact multiple TOPs.</li> </ol> </li> </ul>

### 3.3. TOP Notification Requirements for SOL Exceedances

In accordance with NERC Standard FAC-011-4 R7 and the RC0610 SOL Methodology, TOPs are required to notify the RC Operator of SOL Exceedances on BES facilities in its TOP area within the timeframes specified below, which are categorized based on level of risk to reliability of the BES. This requirement pertains to sustained SOL exceedances, meaning exceedances that are not momentary, based on Operator judgement and discretion. Typically, a momentary exceedance would be an event where the Operator would not normally have adequate time to validate, such as an RTCA exceedance lasting for a single interval or an actual exceedance lasting less than 2 minutes.

**Category 1:** Notify as soon as possible, but no more than 15 minutes after discovering exceedance.

- IROL exceedance
- Actual exceedance of a predetermined stability limit or verified calculated post-contingency results indicates potential for instability
- Verified Insecure Operating State
- Calculated post-contingency exceedance of highest Emergency Rating  $\geq 125\%$
- Actual/pre-Contingency exceedance above the highest Emergency Rating
- Actual/pre-Contingency exceedance above the Normal Rating and of a duration that exceeds the time duration of available Emergency Rating
- Actual/pre-Contingency bus voltage is outside the emergency System Voltage Limits
- Actual/pre-Contingency bus voltage is below the normal low System Voltage Limits and of a duration that exceeds the time duration of available emergency System Voltage Limits
- Calculated Post-contingent exceedance of 100-125% of highest emergency Facility Rating, if not resolved within 30 minutes

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

- Actual/pre-Contingency bus voltage is above the normal high System Voltage Limits and of a duration that exceeds the time duration of available emergency System Voltage Limits, if not resolved within 30 minutes

#### Category 2: Notify within 30 minutes


- Calculated Post-contingency exceedance of emergency High or Low System Voltage Limit, if not resolved within 30 minutes
- Provide within 30 minutes of RC request for a post-contingent mitigation plan for a calculated post-contingency (RTCA) exceedance that a TOP is unable to mitigate in a timely manner by implementing the primary Operating Plan

### 3.4. Actual Thermal SOL Exceedances

When EMS alarms, SCADA, PI, and/or RTSE indicates the actual real-time flows are exceeding the Normal (continuous) Rating for a monitored facility, take the following actions:

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Confirm</b> the condition is real by <b>checking</b> flows, ratings and associated time durations with the TOP. <ul style="list-style-type: none"> <li>○ <b>Validate</b> the quality of the solution if the indication is from RTSE.</li> <li>○ <b>Operate</b> to the <i>most limiting</i> results, in instances where there is disagreement in results between entities.</li> <li>○ <b>Determine</b> whether there is an Emergency Rating available and the associated time duration of the rating of the monitored facility. Exceedance of the normal (continuous) rating, for a duration exceeding the time duration of available Emergency Ratings, is an SOL Exceedance.</li> </ul> </li> <li>• <b>Evaluate</b> the results in <i>RTCA</i> to determine the impact of Contingencies on the monitored facility. RTCA might indicate the need for a more stringent mitigation time.</li> <li>• <b>Contact</b> the TOP for the monitored facility to <b>discuss</b> mitigation plans to avoid exceeding the associated time duration, and expected timeframe for mitigation. <ul style="list-style-type: none"> <li>○ <b>Determine</b> if the exceedance impacts other BA/TOP(s) or if multiple entities would be required for mitigation. If so, <b>initiate</b> a conference call to <b>notify</b> impacted TOPs, BAs, or RCs <u>and</u> to <b>ensure</b> all parties have a common understanding of the mitigation plan and their role within the plan.<sup>6</sup></li> </ul> </li> </ul>

<sup>6</sup> IRO-008-3 R5

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Evaluate</b> the <i>effectiveness</i> of mitigation actions being taken to ensure exceedance will be mitigated within the required mitigation time. Options for mitigation include: <ul style="list-style-type: none"> <li>○ <b>Re-dispatching</b> generation,</li> <li>○ <b>Reconfiguring</b> the transmission system,</li> <li>○ <b>Transferring</b> load out of load pocket,</li> <li>○ <b>Returning</b> scheduled outages,</li> <li>○ <b>Curtailing</b> schedules,</li> <li>○ <b>Using</b> phase shifters, series devices, or HVDC to re-direct flows, and</li> <li>○ <b>Shedding</b> load (<b>Refer to RC0410 System Emergencies, Section 3.5 Load Shedding Instructions</b>).</li> </ul> </li> <li>• <b>Issue</b> an Operating Instruction, including the mitigation actions needed to return the system to within limits within a specified timeframe if the mitigation actions taken or being taken are <u>not</u> appropriate, timely, or sufficient (<b>Refer to RC0410 System Emergencies, Section 3.4 Operating Instructions</b>). See <a href="#">Appendix A</a> for RC mitigation options.</li> <li>• <b>Notify</b> any <i>impacted entity (ies)</i>, as deemed necessary by the RC Operator, once the condition has been mitigated.<sup>7</sup></li> <li>• <b>Log</b> a summary of <i>communications</i> and <i>actions</i> taken to mitigate the exceedance, as well as any SOLs exceeded.</li> </ul>


### 3.5. Actual Voltage SOL Exceedances

When EMS alarms, SCADA, PI, and/or RTSE indicates an actual BES bus/station voltage is outside the normal (continuous) voltage limits for a monitored facility, take the following actions:

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Verify</b> the exceedance being indicated is on an actual BES bus/station monitored by the TOP, and <u>not</u> a fictitious bus in the network model. <b>Note</b> that line side series capacitor/reactor buses and dedicated shunt capacitor/reactor buses, are <u>not</u> monitored by default, unless the TOP states these should be monitored.<sup>8</sup></li> </ul>


<sup>7</sup> IRO-008-3 R6

<sup>8</sup> TOP monitored buses and System Voltage Limits are posted to the RC Portal > Libraries > Studies > SOL Methodology.

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Reliability Coordinator Actions	
<ul style="list-style-type: none"> <li>• <b>Confirm</b> the condition is real by <b>checking</b> voltage, System Voltage Limit, and associated time durations with the TOP. <ul style="list-style-type: none"> <li>○ <b>Validate</b> the quality of the solution if the indication is from RTSE and SCADA is unavailable for the bus/station.</li> <li>○ <b>Operate</b> to the <i>most limiting</i> results in instances where there is disagreement in results between entities.</li> <li>○ <b>Determine</b> the associated time duration of the System Voltage Limit of the bus/station. Exceedance outside the normal System Voltage Limits for longer than the default time duration of 30 minutes (unless the TOP provides a different time duration for the emergency System Voltage Limit) is an SOL Exceedance.</li> </ul> </li> <li>• <b>Evaluate</b> the results in RTCA to determine the impact of Contingencies on the monitored facility. RTCA might indicate the need for a more stringent mitigation time.</li> <li>• <b>Contact</b> the TOP for the monitored facility to <b>discuss</b> the mitigation plan's expected timeframe for mitigation. <ul style="list-style-type: none"> <li>○ For <u>Low</u> Voltage exceedance, <b>contact</b> the TOP within a timeframe that avoids exceeding the associated time duration of the Emergency System Voltage Limit.</li> <li>○ For <u>High</u> Voltage exceedance, <b>contact</b> the TOP if the high Voltage Exceedance has <u>not</u> been mitigated within the associated time duration of the Emergency System Voltage Limit.</li> </ul> </li> <li>• <b>Determine</b> if the exceedance impacts other BA/TOP(s) or if multiple entities would be required for mitigation. If so, <b>initiate</b> a conference call to <b>notify</b> impacted TOPs, BAs, or RCs <u>and</u> to <b>ensure</b> all parties have a common understanding of the mitigation plan and their role within the plan.<sup>9</sup></li> <li>• <b>Evaluate</b> the <i>effectiveness</i> of mitigation actions being taken to ensure exceedance will be mitigated within the required mitigation time. Options for mitigation include: <ul style="list-style-type: none"> <li>○ <b>Switching</b> static reactive devices, such as shunt capacitors and reactors in/out of service,</li> <li>○ <b>Re-dispatching</b> dynamic reactive resources such as synchronous condensers, static VAR compensators (SVCs), HVDC Voltage Source Converters (VSCs), STATCOMs, etc.,</li> <li>○ <b>Using</b> transformer tap changers to redirect reactive flows,</li> <li>○ <b>Issuing</b> revised voltage schedules to synchronized generation,</li> <li>○ <b>Re-dispatching</b> generation/pumps,</li> <li>○ <b>Reconfiguring</b> the transmission system,</li> </ul> </li> </ul>	

<sup>9</sup> IRO-008-3 R5

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Reliability Coordinator Actions	
<ul style="list-style-type: none"> <li>○ <b>Returning</b> scheduled outages,</li> <li>○ <b>Curtailling</b> schedules,</li> <li>○ <b>Using</b> phase shifters, series devices or HVDC to re-direct flows, and</li> <li>○ <b>Shedding</b> load (<b>Refer to RC0410 System Emergencies, Section 3.5 Load Shedding Instructions</b>).</li> <li>● <b>Issue</b> an Operating Instruction, including the mitigation actions needed to return the system to within limits within a specified timeframe if the mitigation actions taken or being taken are <u>not</u> appropriate, timely, or sufficient (<b>Refer to RC0410 System Emergencies, Section 3.4 Operating Instructions</b>).</li> <li>● <b>Notify</b> any impacted entity(ies), as deemed necessary by the RC Operator once the condition has been mitigated.<sup>10</sup></li> <li>● <b>Log</b> a summary of communications and actions taken to mitigate the exceedance, as well as any SOLs exceeded.</li> </ul>	

### 3.6. Actual Stability SOL Exceedances

Stability limits have been established for certain interfaces/paths based on Operations Planning Studies. These limits already have built-in distribution factors that account for the effect of identified single or credible multiple Contingencies. If a stability limit is exceeded the expectation is, a Contingency could cause instability on the system.

Pre-identified stability limits would typically have an associated Operating Plan, Procedure, Process, or memo.


For stability limits pre-established as impacting multiple TOPs, the RC SOL Methodology requires that the RC validate the stability limits. *RC0310A Stability SOLs and Areas with Risk of Localized Voltage Collapse* includes a listing of stability limits that impact multiple TOPs.

#### 3.6.1. RC Validation of Stability Limits Impacting Multiple TOPs

RC West will have a process to validate the stability limit provided by the TOP for path/interfaces that impact multiple TOPs. If available, RC West will utilize RT-VSA or RT-DSA tools to validate the submitted TOP study limit prior to requiring mitigation.

RC West will request the RCOE to initiate validation when real-time flow is within 500 MW of the SOL study limit or the limit calculated by RT-VSA or RT-DSA. If the RC West calculated real-time limit is determined to be correct by the RCOE, the RC Operator will update the RC study limit sent via ICCP.

<sup>10</sup> IRO-008-3 R6

 California ISO   RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

### 3.6.2. Stability Limit Versus TTC


In accordance with the RC SOL Methodology, a path does not have a single uniquely monitored SOL unless the path is associated with an established transient or voltage stability limit. RC West's stability analysis tools calculate the SOL by stressing the path to determine the transient or voltage stability limits, and not based on thermal or steady-state voltage limits.

When validating the path limit provided by the TOP against RC West's Real-time stability analysis tools, the RC Operator will determine whether the limit calculated by the TOP is a true stability limit or a Total Transfer Capability (TTC). A path TTC may be established by a TOP based on pre- or post-contingency thermal or steady-state voltage limits, or based on a WECC path rating; however, simply exceeding a path TTC does not constitute an SOL exceedance. If real time assessment indicates a pre or post-contingency contingency SOL exceedance or potential insecure operating state, curtailing path TTC may be viable mitigation option.

RC West will ensure that the RC study limit sent via ICCP for stability limits impacting multiple TOPs represents a true stability limit and not just a TTC. In addition, RC West will require mitigation within 30 minutes only when the validated RC study limit is exceeded.

The RC Operator will take the following actions in validating and setting the RC study limit.

Reliability Coordinator Actions	
<ul style="list-style-type: none"> <li>• <b>Request</b> the RCOE to validate the limit indicated in RC West RT-VSA or RT-DSA tool.</li> <li>• <b>Determine</b> if the TOP provided limit for the path/interface is stability-based, based on thermal or steady-state voltage limits, or based on a WECC path rating. <ul style="list-style-type: none"> <li>○ If the limit provided by the TOP is stability-based, <b>determine</b> why there is discrepancy in limits. If there is disagreement, <b>set</b> the RC study limit to the most-limiting of the results from the RC and TOP tools.</li> <li>○ If the limit provided by the TOP is based on thermal or steady-state voltage, or based on a WECC path rating, set the RC study limit based on the results of only RC West's RT-VSA or RT-DSA tool.</li> </ul> </li> <li>• <b>Require</b> mitigation within 30 minutes, only when the RC study limit is exceeded.</li> </ul>	


 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

### 3.6.3. RC Actions to Mitigate Stability Limit Exceedance

When RT Assessments indicate the flow on an interface/path is exceeding a pre-determined stability limit, take the following actions:

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Confirm</b> the <i>stability limit</i> and flows with the TOP. <ul style="list-style-type: none"> <li>○ <b>Ensure</b> the <i>revised limits</i> are <i>properly coordinated</i> with impacted entity(ies) if the TOP provides a revised stability limit. <ul style="list-style-type: none"> <li>▪ If there is available real-time calculation of stability limit based on RC West RT-VSA or RTDSA tools, <b>ensure</b> that the limit is validated and updated <b>in accordance with</b> Sections <a href="#">3.6.1</a> and <a href="#">3.6.2</a>.</li> </ul> </li> <li>○ <b>Operate</b> to the <i>most limiting</i> results in instances where there is disagreement in results between entities.</li> </ul> </li> <li>• <b>Determine</b> the <i>mitigation actions</i> and <i>mitigation time</i> from available pre-determined Operating Plans, Procedures, Processes, or memos for the limit.</li> <li>• <b>Determine</b> if the exceedance impacts other BA/TOP(s) or if multiple entities would be required for mitigation. If so, <b>initiate</b> a conference call to <b>notify</b> impacted TOPs, BAs, or RCs <u>and</u> to <b>ensure</b> all parties have a common understanding of the mitigation plan and their role within the plan.<sup>11</sup></li> <li>• <b>Evaluate</b> the effectiveness of mitigation actions being taken by the TOP to ensure exceedance will be mitigated within the required mitigation time. Options for mitigation include: <ul style="list-style-type: none"> <li>○ <b>Re-dispatching</b> generation,</li> <li>○ <b>Reconfiguring</b> the transmission system,</li> <li>○ <b>Transferring</b> load out of area with stability concern,</li> <li>○ <b>Returning</b> scheduled outages,</li> <li>○ <b>Curtailing</b> schedules,</li> <li>○ <b>Using</b> phase shifters, series devices, or HVDC to redirect flows,</li> <li>○ <b>Requesting</b> unscheduled flow (USF) mitigation for qualified paths, and</li> <li>○ <b>Shedding</b> load (<b>Refer to RC0410 System Emergencies, Section 3.5 Load Shedding Instructions</b>).</li> </ul> </li> <li>• For a Voltage Stability exceedance, options for mitigation also include: <ul style="list-style-type: none"> <li>○ <b>Switching</b> static reactive devices, such as shunt capacitors and reactors in/out of service,</li> </ul> </li> </ul>

<sup>11</sup> IRO-008-3 R5

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>○ <b>Re-dispatching</b> dynamic reactive resources, such as synchronous condensers, static VAR compensators (SVCs), HVDC Voltage Source Converters (VSCs), STATCOMs, etc.,</li> <li>○ <b>Using</b> transformer tap changers to redirect reactive flows, and</li> <li>○ <b>Issuing</b> revised voltage schedules to synchronized generation.</li> <li>● <b>Issue</b> an <i>Operating Instruction</i> with the mitigation actions to take to return the system to within limits within a specified timeframe if the mitigation actions taken or being taken are <u>not</u> appropriate, timely, or sufficient (<b>Refer to RC0410 System Emergencies, Section 3.4 Operating Instructions</b>). See <a href="#">Appendix A</a> for RC mitigation options.</li> <li>● <b>Notify</b> the <i>impacted entity(ies)</i> of the exceedance and the mitigation once completed,<sup>12</sup> if it impacts or potentially impacts neighboring TOPs, BAs, or RCs. If necessary, <b>initiate</b> a conference call with the affected parties.</li> <li>● <b>Notify</b> any <i>impacted entity(ies)</i>, as deemed necessary by the RC Operator, once the condition has been mitigated.<sup>13</sup></li> <li>● <b>Log</b> a summary of <i>communications</i> and <i>actions</i> taken to mitigate the exceedance, as well as any SOLs exceeded.</li> </ul>


### 3.7. RTCA Post-Contingency Thermal SOL Exceedances

When RTCA results indicate calculated post-Contingency flow will exceed the highest Emergency (Short-Term) Rating for a monitored facility, an SOL is being exceeded, and actions must be taken to mitigate the exceedance *pre-Contingency*.

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>● <b>Validate</b> the <i>results</i> and <i>limits</i> used in RTCA: <ul style="list-style-type: none"> <li>○ <b>Check</b> RTSE solution quality.</li> <li>○ <b>Verify</b> if any RAS(s) is associated with the Contingency and the status.</li> <li>○ <b>Use</b> a DLF and CA <i>study</i> tool as needed to <b>verify</b> the results.</li> <li>○ <b>Verify</b> the contingency definition.</li> <li>○ <b>Request</b> a study by the RCOE.</li> </ul> </li> </ul>

<sup>12</sup> IRO-008-3 R5, R6

<sup>13</sup> IRO-008-3 R6


 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Reliability Coordinator Actions	
<ul style="list-style-type: none"> <li>• <b>Verify</b> results with the TOP <u>and</u> <b>determine</b> whether the TOP's <i>Real-time Assessment</i> indicates the same exceedance. <ul style="list-style-type: none"> <li>○ <b>Operate</b> to the <i>most limiting</i> RTCA results in instances where there is disagreement on the results.</li> </ul> </li> <li>• <b>Refer</b> to <a href="#">Section 3.9</a> if results indicate any post-Contingency <i>exceedance greater than 125%</i>.</li> <li>• <b>Review</b> the contingent and monitored element to determine if multiple entities are impacted or if multiple entities would be required for mitigation. If so, <b>initiate</b> a conference call to <b>notify</b> impacted TOPs, BAs, or RCs <u>and</u> to <b>ensure</b> all parties have a common understanding of the mitigation plan and their role within the plan. <sup>14</sup></li> <li>• <b>Evaluate</b> the <i>effectiveness</i> of mitigation actions being taken. Pre-contingency mitigation is required if mitigation options are available. Options for mitigation include: <ul style="list-style-type: none"> <li>○ <b>Re-dispatching</b> generation,</li> <li>○ <b>Reconfiguring</b> the transmission system,</li> <li>○ <b>Transferring</b> load out of area,</li> <li>○ <b>Returning</b> scheduled outages,</li> <li>○ <b>Curtailling</b> schedules, and</li> <li>○ <b>Using</b> phase shifters, series devices, or HVDC to re-direct flows.</li> </ul> </li> <li>• <b>Require</b> the TOP to provide a <i>viable post-Contingency mitigation plan within 30 minutes</i>, <sup>15</sup> if the pre-contingent exceedance cannot be mitigated by implementing the primary Operating Plan, which would include actions up to and including post-contingent load shedding. (<b>Refer</b> to <a href="#">Section 3.13</a> Post-Contingency Mitigation Plans).</li> </ul> <p><b>Notes:</b></p> <ul style="list-style-type: none"> <li>– <i>Planned manual load shedding is acceptable only after all other available System adjustments have been made pre-contingency.</i> <sup>16</sup></li> <li>– <i>If the required System adjustments could impact delivery of energy to an energy deficient BA in EEA 3, the RC would accept an Operating Plan that includes planned manual or automatic post-Contingent load shedding, provided the Contingency would <u>not</u> result in instability, Cascading, or uncontrolled separation that adversely impact the reliability of the BES.</i></li> </ul>	

<sup>14</sup> IRO-008-3 R5

<sup>15</sup> The 30-minute requirement starts when the RC Operator requests for the plan from the TOP.

<sup>16</sup> Refer to RC0610 SOL Methodology Section G on Acceptable System Performance.

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Issue</b> an <i>Operating Instruction</i>, including the mitigation actions needed to return the system to within limits within a specified timeframe if the mitigation actions taken or being taken, are <u>not</u> appropriate, timely, or sufficient (<b>Refer to RC0410 System Emergencies, Section 3.4 Operating Instructions</b>). See <a href="#">Appendix A</a> for RC mitigation options.</li> <li>• <b>Notify</b> any <i>impacted entity(ies)</i>, as deemed necessary by the RC Operator, once the condition has been mitigated.<sup>17</sup></li> <li>• <b>Log</b> a summary of <i>communications</i> and <i>actions</i> taken to mitigate the exceedance, as well as any SOLs exceeded.</li> </ul>


### 3.8. RTCA Post-Contingency Voltage SOL Exceedances

When RTCA results indicate calculated post-Contingency bus voltage will be outside the Emergency (Short-Term) limits for a monitored facility, an SOL is being exceeded, and actions must be taken to mitigate the exceedance *pre-Contingency*.

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Verify</b> the exceedance being indicated is on an actual BES bus/station monitored by the TOP, and <u>not</u> a fictitious bus in the network model. <b>Note</b> that line side series capacitor/reactor buses and dedicated shunt capacitor/reactor buses, are <u>not</u> monitored by default, unless the TOP states these should be monitored.<sup>18</sup></li> <li>• <b>Validate</b> the <i>results</i> and <i>limits</i> used in RTCA: <ul style="list-style-type: none"> <li>○ <b>Check</b> RTSE solution quality.</li> <li>○ <b>Verify</b> if any RAS(s) is associated with the Contingency and the status.</li> <li>○ <b>Determine</b> if there are automatic voltage regulating shunt capacitors or reactors <u>not</u> accounted for in the RTCA post-contingent solution.</li> <li>○ <b>Use</b> DLF and CA <i>study</i> tool as needed to verify the results.</li> <li>○ <b>Verify</b> the Contingency definition.</li> <li>○ <b>Request</b> a study by the RCOE.</li> </ul> </li> <li>• <b>Verify</b> results with the TOP <u>and</u> <b>determine</b> whether the <i>TOPs Real-time Assessment</i> indicates the same exceedance. <ul style="list-style-type: none"> <li>○ <b>Operate</b> to the <i>most limiting</i> RTCA results in instances where there is disagreement on the results.</li> </ul> </li> </ul>

<sup>17</sup> IRO-008-3 R6

<sup>18</sup> TOP monitored buses and System Voltage Limits are posted to the RC Portal > Libraries > Studies > SOL Methodology.


 California ISO	RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
			Version No.	2.2
			Effective Date	5/14/25
Mitigating SOL and IROL Exceedances			Distribution Restriction: None	

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Refer</b> to <a href="#">Section 3.9</a>, if calculated post-Contingency results indicate <i>potential voltage collapse</i>.</li> <li>• <b>Review</b> the contingent and monitored element to determine if multiple entities are impacted or if multiple entities would be required for mitigation. If so, <b>initiate a conference call to notify</b> impacted TOPs, BAs, or RCs <b>and to ensure</b> all parties have a common understanding of the mitigation plan and their role within the plan.<sup>19</sup></li> <li>• <b>Evaluate</b> the <i>effectiveness</i> of mitigation actions being taken. Pre-contingency mitigation is required if mitigation options are available. Options for mitigation include: <ul style="list-style-type: none"> <li>○ <b>Switching</b> static reactive devices, such as shunt capacitors and reactors in/out of service,</li> <li>○ <b>Re-dispatching</b> dynamic reactive resources, such as synchronous condensers, static VAR compensators (SVCs), HVDC Voltage Source Converters (VSCs), etc.</li> <li>○ <b>Using</b> transformer tap changers to redirect reactive flows,</li> <li>○ <b>Issuing</b> revised voltage schedules to synchronized generation,</li> <li>○ <b>Re-dispatching</b> generation/pumps,</li> <li>○ <b>Reconfiguring</b> the transmission system,</li> <li>○ <b>Transferring</b> load out of collapse zone,</li> <li>○ <b>Returning</b> scheduled outages,</li> <li>○ <b>Curtailing</b> schedules, and</li> <li>○ <b>Using</b> phase shifters, series devices, or HVDC to re-direct flows.</li> </ul> </li> <li>• <b>Require</b> the TOP to provide a <i>viable post-Contingency mitigation plan within 30 minutes</i>,<sup>20</sup> which would include actions up to and including post-contingent load shedding, if the pre-contingent exceedance cannot be mitigated by implementing the primary Operating Plan (Refer to <a href="#">Section 3.13</a>: Post-Contingency Mitigation Plans).</li> <li>• <b>Issue</b> an Operating Instruction, <b>including</b> the mitigation actions needed to return the system within limits within a specified timeframe if the mitigation actions taken or being taken are <b>not</b> appropriate, timely, or sufficient (<b>Refer to RC0410 System Emergencies, Section 3.4 Operating Instructions</b>).</li> <li>• <b>Notify</b> any <i>impacted entity(ies)</i>, as deemed necessary by the RC Operator, once the condition has been mitigated.<sup>21</sup></li> </ul>

<sup>19</sup> IRO-008-3 R5

<sup>20</sup> The 30-minute requirement starts when the RC Operator requests for the plan from the TOP.

<sup>21</sup> IRO-008-3 R6

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Log</b> a summary of <i>communications</i> and <i>actions</i> taken to mitigate the exceedance, as well as any SOLs exceeded.</li> </ul>

### 3.9. IROL Exceedances

For each IROL identified one or more days prior to the current day, RC West has an Operating Plan that identifies actions the RC shall take or direct others to take (up to and including load shedding), which can be implemented in time to prevent the identified IROL exceedance within IROL T<sub>v</sub>.<sup>22</sup> The default IROL T<sub>v</sub> is 30 minutes, unless conditions require a shorter T<sub>v</sub>.


When EMS alarms, SCADA, PI, and/or RTSE indicate the actual Real-time flow on an interface/path is exceeding a pre-determined IROL limit; or RTCA or RT-VSA indicates a single or credible multiple Contingency will result in exceeding a pre-determined IROL limit, take the following actions:

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Validate</b> the <i>results</i> and <i>limits</i> used in the application if the exceedance is based on RTCA or RT-VSA results: <ul style="list-style-type: none"> <li>○ <b>Check</b> RTSE solution quality.</li> <li>○ <b>Verify</b> if any RAS(s) is associated with the Contingency and the status.</li> <li>○ <b>Use</b> DLF and CA study tool as needed to <b>verify</b> the results.</li> </ul> </li> <li>• <b>Confirm</b> the <i>IROL limit</i> and flows with the TOP if the exceedance is based on real-time flows on an IROL interface/path, <ul style="list-style-type: none"> <li>○ <b>Ensure</b> the <i>revised limits</i> are <i>properly coordinated</i> with impacted BA/TOP and the RC if the TOP provides a revised IROL limit.</li> <li>○ <b>Operate</b> to the <i>most limiting</i> IROL and T<sub>v</sub> in instances where there is disagreement in results between entities.</li> </ul> </li> <li>• <b>Review</b> the applicable <i>IROL Operating Plan</i> <u>and</u> <b>determine</b> the required <i>mitigation actions</i>.<sup>23</sup></li> <li>• <b>Determine</b> (from the TOP) the amount of time needed to shed load, if required.</li> <li>• <b>Notify</b> the <i>impacted entity(ies)</i> of the exceedance,<sup>24</sup> if it impacts or potentially impacts neighboring TOPs, BAs, or RCs. If necessary, <b>initiate</b> a conference call with the affected parties.</li> </ul>

<sup>22</sup> IRO-009-2 R1

<sup>23</sup> IRO-009-2 R2

<sup>24</sup> IRO-008-3 R5

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Evaluate</b> the <i>effectiveness</i> of mitigation actions being taken by the TOP to <b>ensure</b> exceedance will be <i>mitigated within 30 minutes</i> (IROL Tv).</li> <li>• <b>Issue</b> an <i>Operating Instruction</i> immediately, if the actions being taken by the TOP will <u>not</u> resolve the exceedance within the 30-minute Tv.</li> <li>• <b>Issue</b> an Operating Instruction without delay, to <b>shed</b> load (within the amount of time the TOP requires to accomplish it) to <b>ensure</b> the exceedance is resolved within the 30-minute Tv,<sup>25</sup> if further evaluation of the mitigation actions indicates the exceedance will <u>not</u> be mitigated within the 30-minute Tv (<i>Refer to RC0410 System Emergencies, Section 3.4 Operating Instructions</i>).</li> <li>• <b>Notify</b> any impacted entity(ies) <i>in accordance with applicable IROL Operating Guide</i>.<sup>26</sup></li> <li>• <b>Log</b> a summary of <i>communications</i> and <i>actions</i> taken to mitigate the exceedance, as well as any IROLs exceeded.</li> </ul>

### 3.10. Insecure Operating State


When RTCA, RT-DSA, or RT-VSA indicates a single or credible multiple Contingency will result in *instability, cascading outages, or voltage collapse*, which was not identified one or more days prior to the current day,<sup>27</sup> the system is considered to be in an insecure operating state once the condition is verified. In this scenario, although an IROL was not previously identified, the exceedance of an unidentified IROL cannot be ruled out. Therefore, System Operators should focus on communicating the urgency to the impacted BA/TOP(s) and RC(s) and returning the system to a secure operating state immediately. A return to a secure operating state should be based on an updated study and mitigating actions up to, and including shedding load. An after-the-fact analysis should explore whether an IROL and/or an area specific operating guide should be established for future similar real-time conditions.

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Validate</b> the results and limits used in the solution: <ul style="list-style-type: none"> <li>○ <b>Check</b> RTSE solution quality.</li> <li>○ <b>Verify</b> if any RAS(s) is associated with the Contingency and the status.</li> <li>○ <b>Verify</b> the Contingency definition.</li> <li>○ <b>Request</b> a study by the RCOE.</li> </ul> </li> </ul>


<sup>25</sup> IRO-009-2 R3

<sup>26</sup> IRO-008-3 R6

<sup>27</sup> IRO-009-2 R1

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Reliability Coordinator Actions	
<ul style="list-style-type: none"> <li>• <b>Run</b> a cascading test if RTCA indicates exceedance greater than 125% of the <i>highest Emergency Rating</i> of a monitored facility, or the facility's relay trip setting (if known), whichever is lower.</li> </ul>	
<div style="border: 1px solid black; padding: 10px; margin: 10px 0;"> <p><b><u>Cascading Test</u></b></p> <ol style="list-style-type: none"> <li>1. <b>Load</b> the RTSE case into the CA study tool.</li> <li>2. <b>Take out of service</b> the contingent element and the monitored element.</li> <li>3. <b>Run</b> power flow study.</li> <li>4. <b>Determine</b> if any facilities will be loaded above 125% of the highest Emergency rating, or the facility's relay trip setting (if known), whichever is lower.</li> <li>5. <b>Take out of service</b> any facility that meets the criteria in Step 4.</li> <li>6. <b>Repeat</b> Steps 3 to 5 until no facility meets the criteria in Step 4, or until the solution diverges.</li> </ol> <p><b>Note:</b> A diverged solution may indicate a potential voltage collapse.</p> </div>	
<ul style="list-style-type: none"> <li>• <b>Contact</b> the TOP to <b>verify</b> results <u>and</u> <b>determine</b> whether the <i>TOPs Real-time Assessment</i> indicates the same condition. <ul style="list-style-type: none"> <li>○ <b>Operate</b> to the <i>most limiting</i> RTCA results in instances where there is disagreement on the results.</li> </ul> </li> <li>• <b>Declare</b> an insecure operating state, by <b>notifying</b> the TOP by phone <u>and</u> <b>following up</b> with a GMS message without intentional delay, as soon as instability, cascading outages, or voltage collapse indications are verified (<b>Refer to RC0310C Guidelines for Declaring Insecure Operating State</b>). If necessary, <b>initiate</b> a conference call with the affected party(s).</li> <li>• <b>Require</b> the TOP to start taking <i>mitigation actions</i>. The insecure operating state <b>must be mitigated within 30 minutes</b> from the time the insecure operating state was declared.</li> <li>• <b>Evaluate</b> the <i>effectiveness</i> of mitigation actions being taken by the TOP. Options for mitigation include: <ul style="list-style-type: none"> <li>○ <b>Re-dispatching</b> generation,</li> <li>○ <b>Reconfiguring</b> the transmission system,</li> <li>○ <b>Transferring</b> load out of the zone,</li> <li>○ <b>Returning</b> scheduled outages,</li> </ul> </li> </ul>	

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>○ <b>Curtailing</b> schedules,</li> <li>○ <b>Using</b> phase shifters, series devices, or HVDC to re-direct flows,</li> <li>○ <b>Requesting</b> unscheduled flow (USF) mitigation for qualified paths, and</li> <li>○ <b>Shedding</b> load (<b>Refer</b> to <i>RC West RC0410 System Emergencies, Section 3.5: Load Shedding</i>).</li> <li>● <b>Issue</b> an Operating Instruction to <b>shed</b> load (within the amount of time the TOP requires to accomplish it) to <b>ensure</b> the insecure operating state is resolved within the 30-minute timeframe, if further evaluation of the mitigation actions indicates the insecure operating state will <u>not</u> be mitigated within the 30-minute timeframe.<sup>28</sup> (<b>Refer</b> to <i>RC West Operating Procedure RC0410 System Emergencies, Section 3.4 Operating Instructions</i>).</li> <li>● <b>Notify</b> impacted BA(s), TOP(s) and RC(s) <b>via</b> GMS once the condition has been mitigated.<sup>29</sup></li> <li>● <b>Log</b> a summary of <i>communications</i> and <i>actions</i> taken to mitigate the insecure operating state.</li> </ul>

### 3.11. Unsolved Contingencies in RTCA

A Contingency that fails to converge in RTCA may be an indication of a potential voltage collapse or other infeasible operating state that might occur if the Contingency actually happened.

On the other hand, an unsolved Contingency might also indicate a modelling error or other data problem, which could degrade the quality of the base case. Such errors could degrade the quality of the results for all Contingencies, even those that solve successfully.<sup>30</sup> If left unresolved, situational awareness of potential SOL or IROL violations is compromised until personnel can identify the cause of the unsolved Contingency.<sup>31</sup>


Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>● <b>Request</b> RCOE and EMS <i>Engineering support</i> to investigate and resolve the causal factors related to input data, the model, or the RTCA application itself.</li> <li>● <b>Run study</b> of the Contingency in question, <b>using</b> DLF and CA study tools.</li> <li>● <b>Verify</b> results with the TOP <u>and</u> <b>determine</b> whether the <i>TOPs Real-time Assessment</i> indicates the same exceedance.</li> </ul>

<sup>28</sup> IRO-009-2 R3

<sup>29</sup> IRO-008-3 R6

<sup>30</sup> IRO-018-1(i) R2.3.

<sup>31</sup> NATF Operator Tools & Environment – Contingency Analysis Practices

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>○ <b>Operate</b> to the <i>most limiting</i> results in instances where there is disagreement.</li> <li>● <b>Assume</b> a <i>conservative approach</i>, because the post-Contingency operating state is most likely unstable or in a voltage collapse. Refer to <a href="#">Section 3.10</a>: Insecure Operating State.</li> <li>● <b>Log</b> each <i>unsolved Contingency</i>, verbal discussions, related studies, and <i>actions</i> taken to resolve it.</li> </ul>

### 3.12. Islanding Conditions

RC West RTCA will identify islands greater than 100 MW that will result from a single or credible multiple Contingency. Contingencies creating islands are not SOLs or IROLs; however, the RC will notify the impacted TOPs, BAs, and RCs for situational awareness.


Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>● <b>Validate</b> the <i>islanding</i> condition in RTCA. <ul style="list-style-type: none"> <li>○ <b>Verify</b> the Contingency definition.</li> <li>○ <b>Verify</b> the topology in the model.</li> <li>○ <b>Use</b> DLF and CA <i>study</i> tool as needed to <b>verify</b> the results.</li> <li>○ <b>Request</b> a study by the RCOE.</li> </ul> </li> <li>● <b>Notify</b> the impacted TOPs, BAs, and RCs of the Contingency creating an island for situational awareness.</li> </ul>

### 3.13. Post-Contingency Mitigation Plans

A TOP must provide a viable post-Contingency mitigation plan if it is unable to mitigate an SOL pre-Contingency in a timely manner due to generation startup, ramp rate, or other constraints; or if there are no automatic post-Contingency actions such as RAS/SPS that can resolve the issue. A post-Contingency mitigation plan is considered viable and acceptable by the RC when:

- The limitation in question is not an IROL, stability limit, or Insecure Operating State.
- The plan can be implemented in a timely manner without adverse reliability consequences.
- The RC confirms the plan will resolve the reliability issue in a timely manner.
- All impacted BAs, TOPs, and RCs agree with the plan.

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>● <b>Ensure</b> the <i>TOP understands</i> the limiting Contingency and monitored facility.</li> </ul>

 California ISO   RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Require</b> the <i>TOP</i> to provide the <i>specifics</i> of the plan and the <i>time to implement</i>.</li> <li>• <b>Ensure</b> the plan meets the four criteria described above.</li> <li>• <b>Request</b> a study by the RCOE if needed.</li> <li>• <b>Log</b> all <i>communications</i> and the specifics of the <i>plan</i>.</li> </ul>

### 3.14. Change of RAS Status


Accurate RAS monitoring is necessary to perform Real-time Assessments in order to identify facilities approaching SOL and IROL limits; and to identify SOL and IROL exceedances within the RC West Area. The applicable TOP shall notify the RC if there is a change in RAS status according to RC0130 Reporting Requirements for Real-Time Events.

Reliability Coordinator Actions
<ul style="list-style-type: none"> <li>• <b>Receive</b> notification from EMS, GMS, or phone that there has been a change in status for one or more RAS.</li> <li>• <b>Verify</b> with the <i>TOP</i> that the RAS status has changed and the reason for the change.</li> <li>• <b>Request</b> the TOP to submit an OMS outage if the RAS is forced out of service for more than 30 minutes.</li> <li>• <b>Notify</b> the RCOE of the change in RAS status.</li> <li>• <b>Notify</b> the impacted TOPs, BAs, and RCs of the RAS status change for situational awareness.</li> <li>• <b>Verify</b> that the RAS modeling is correctly reflected in RTCA.</li> <li>• <b>Request</b> a study by the RCOE if needed.</li> <li>• <b>Log</b> all <i>communications</i> and the specifics of the change in RAS status.</li> </ul>

## 4. Supporting Information

### Operationally Affected Parties

Shared with the Public; additionally shared with AESO, BCRC, and SPP RC.

 California ISO   RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	


## References

NERC Requirements	FAC-011-4 R7; FAC-014-3  IRO-002-7 R5; IRO-006-5 R1; IRO-006-WECC-3 R1; IRO-008-3 R4 - R6; IRO-009-2 R1 - R4; IRO-014-3 R1; IRO-018-1(i) R2.3.
BATOP Operating Procedure	
RC West Operating Procedures	<a href="#">RC0310A Stability SOLs and Areas with Risk of Localized Voltage Collapse</a> <a href="#">RC0310C Guidelines for Declaring Insecure Operating State</a> <a href="#">RC0410 System Emergencies</a> <a href="#">RC0520 Loss of Monitoring and Analysis Tools</a> <a href="#">RC0610 SOL Methodology for the Operations Horizon</a> <a href="#">RC9010 Unscheduled Flow Mitigation on Qualified Paths</a>
Other References	NATF Operator Tools & Environment – Contingency Analysis Practices  Western Interconnection Unscheduled Flow Mitigation Plan


## Definitions

The following terms capitalized in this Operating Procedure are in accordance with the NERC Glossary, and/or otherwise when used are as defined below:


Term	Description
Energy Management System (EMS)	An application used to perform real-time monitoring, analysis, real-time coordination, and generation control. Reliability entities provide telemetered data to CAISO EMS. Generators and CAISO Market Participants receive data and control signals from CAISO EMS.
Inter-Control Center Communication Protocol (ICCP)	Provides a standard format for exchanging data between system and/or entities.
PT RTCA	Backup RTCA tool

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Term	Description
Remedial Action Schemes (RAS)	<p>A scheme designed to detect predetermined System conditions and automatically take corrective actions that may include, but are not limited to adjusting or tripping generation (MW and Mvar), tripping load, or reconfiguring a System(s). RAS accomplish objectives, such as:</p> <ul style="list-style-type: none"> <li>• Meet requirements identified in the NERC Reliability Standards</li> <li>• Maintain Bulk Electric System (BES) stability</li> <li>• Maintain acceptable BES voltages</li> <li>• Maintain acceptable BES power flows</li> <li>• Limit the impact of Cascading or extreme events</li> </ul> <p>The following do not individually constitute a RAS:</p> <ul style="list-style-type: none"> <li>• Protection Systems installed for the purpose of detecting Faults on BES Elements and isolating the faulted Elements</li> <li>• Schemes for automatic underfrequency load shedding (UFLS) and automatic undervoltage load shedding (UVLS) comprised of only distributed relays</li> <li>• Out-of-step tripping and power swing blocking</li> <li>• Automatic reclosing schemes</li> <li>• Schemes applied on an Element for non-Fault conditions, such as, but not limited to generator loss-of-field, transformer top-oil temperature, overvoltage or overload to protect the Element against damage by removing it from service</li> </ul>
System Operating Limit (SOL)	All Facility Ratings, System Voltage Limits, and stability limits applicable to specified System configurations used in Bulk Electric System operations for monitoring and assessing pre- and post- Contingency operating states.
System Voltage Limit	The maximum and minimum steady-state voltage limits (both normal and emergency) that provide for acceptable System performance.
Interconnection Reliability Operating Limit (IROL)	A System Operating Limit that if violated, could lead to instability, uncontrolled separation, or Cascading outages that adversely impact the reliability of the Bulk Electric System.

 California ISO   RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	


Term	Description
IROL Tv	The maximum time that an Interconnection Reliability Operating Limit can be violated before the risk to the interconnection or other Reliability Coordinator Area(s) becomes greater than acceptable. Each Interconnection Reliability Operating Limit's Tv shall be less than or equal to 30 minutes.
SCADA	Supervisory Control and Data Acquisition
Reliability Coordinator (RC) Area	The collection of generation, transmission, and loads within the boundaries of the Reliability Coordinator. Its boundary coincides with one or more Balancing Authority Areas.
Normal (Continuous) Ratings	The rating as defined by the equipment owner that specifies the level of electrical loading, usually expressed in megawatts (MW) or other appropriate units, that a system, facility, or element can support or withstand through the daily demand cycles without loss of equipment life.
Emergency (Short-Term) Rating	The rating as defined by the equipment owner that specifies the level of electrical loading or output, usually expressed in megawatts (MW) or Mvar or other appropriate units, that a system, facility, or element can support, produce, or withstand for a finite period. The rating assumes acceptable loss of equipment life or other physical or safety limitations for the equipment involved.
Operating Plan	A document that identifies a group of activities that may be used to achieve some goal. An Operating Plan may contain Operating Procedures and Operating Processes. A company-specific system restoration plan that includes an Operating Procedure for black-starting units, Operating Processes for communicating restoration progress with other entities, etc., is an example of an Operating Plan.
Operating Procedure	A document that identifies specific steps or tasks that should be taken by one or more specific operating positions to achieve specific operating goal(s). The steps in an Operating Procedure should be followed in the order in which they are presented, and should be performed by the position(s) identified. A document that lists the specific steps for a system operator to take in removing a specific transmission line from service is an example of an Operating Procedure.

	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Term	Description
Operating Process	A document that identifies general steps for achieving a generic operating goal. An Operating Process includes steps with options that may be selected, depending upon Real-time conditions. A guideline for controlling high voltage is an example of an Operating Process.
Real-time Assessment	An evaluation of system conditions using Real-time data to assess existing (pre-Contingency) and potential (post-Contingency) operating conditions. The assessment shall reflect applicable inputs including, but not limited to: load, generation output levels, known Protection System and Special Protection System status or degradation, Transmission outages, generator outages, Interchange, Facility Ratings, and identified phase angle and equipment limitations. (Real-time Assessment may be provided through internal systems or through third-party services.)
Contingency	The unexpected failure or outage of a system component, such as a generator, transmission line, circuit breaker, switch, or other electrical element.

## Version History

Version	Change	Date
1.5	Section 3.9: Removed references of RCIS. Replaced Peak RC with SPP West RC or impacted RC. Updated NERC IRO-002 reference. Clarified RC Operator notification requirements after an exceedance is mitigated in Sections 3.3 to 3.8.	5/12/20
1.6	Section 3.2: Added footnote NERC Standard IRO-009-2 R4. Removed and merged Section 14 of RC0310 and RC0310B content into RC9010 procedure. Updated Operationally Affected Parties to include Neighboring RCs in addition to Public sharing. Updated NERC Standard references and added IRO-009-2 R4 to References Section. Removed RC0310 from Appendix list as it is being retired with the publish of RC9010. Minor format and grammar updates. Changes reviewed and approved by the Real-Time Working Group (RTWG).	6/11/21
1.7	Periodic Review: Added Appendix A and references to it in Sections 3.3, 3.5, 3.6. Section 3.5: Added bullet and sub-bullets for a Voltage Stability exceedance. Updated NERC Standard references and minor format and grammar updates throughout. Added procedure references to RC0310A and RC0310B in References section.	5/15/22

 California ISO RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

Version	Change	Date
2.0	Major revisions to several sections to align procedure with revised FAC-011-4 and revised RC0610 SOL Methodology, which will be effective April 1, 2024. Retired RC0130A (effective 4/01/24), and incorporated SOL Reporting Guidelines into new Section 3.3 (TOP Notification Requirements for SOL Exceedances). Revised definition of System Operating Limit (SOL), and added definition for System Voltage Limit, to align with updated definitions in NERC Glossary. (Update was approved by the RTWG.)	4/01/24
2.1	Section 3.2: Added evaluation to identify SOL exceedance for stability path impacting multiple TOPs. Section 3.6: Added language and steps for RC West validation of stability SOL that impact multiple TOPs. References: Added FAC-014-3 to NERC Requirements. Minor formatting and grammar edits.	10/01/24
2.2	Periodic Review: Added new Section 3.6.2 to address how the RC treats stability limit versus TTC. Minor formatting and grammar edits and removed history prior to five years.	5/14/25

## 5. Periodic Review Procedure


### Review Criteria & Incorporation of Changes

There are no specific review criteria identified for this document.

### Frequency

Review at least once every three years.

**See Appendix A: RC Exceedance Mitigation Steps on the following page.**

 California ISO   RC West	Reliability Coordinator Procedure	Procedure No.	RC0310
		Version No.	2.2
		Effective Date	5/14/25
Mitigating SOL and IROL Exceedances		Distribution Restriction: None	

## Appendix A: RC Exceedance Mitigation Steps

The RC West Reliability Coordinator has the authority to implement congestion management steps in any order; however, the generally preferred order of actions is:

- 1) Security constrained market re-dispatch (if available)
- 2) Operating phase-shifting and series devices, including Unscheduled Flow Mitigation (if qualified)
- 3) Low-risk pre-contingency transmission reconfiguration
- 4) Transferring load out of the area
- 5) Returning scheduled outages
- 6) Manual re-dispatch of generation and/or HVDC devices within the affected TOP area
- 7) Cutting Path schedules and reducing TTCs (if constraint is related to one or more scheduling Paths)
- 8) Starting or shutting down generation within the affected TOP area
- 9) Other pre-contingency transmission reconfiguration
- 10) Manual generation re-dispatch instruction to generation and/or HVDC devices outside of the affected TOP area, by order of effectiveness
- 11) Starting or shutting down generation outside of the affected TOP area, by order of effectiveness
- 12) Shedding firm load