

Alhambra

- (a) all 230 kV and lower voltage transmission lines and associated station equipment identified in the ISO Register as that portion of the ISO Controlled Grid located in the SCE Service Area.

San Diego

- (a) all 230 kV and lower voltage transmission lines and associated station equipment identified in the ISO Register as that portion of the ISO Controlled Grid located in the SDGE Service Area.

OCP 1.2 Definitions

OCP 1.2.1 Master Definitions Supplement

Unless the context indicates otherwise, any word or expression defined in the Master Definitions Supplement to the ISO Tariff shall have the same meaning where used in this Protocol. A reference to a Section or an Appendix refers to a Section or an Appendix of the ISO Tariff unless otherwise indicated. References to OCP are to this Protocol or to the stated paragraph of this Protocol.

OCP 1.2.2 Special Definitions for this Protocol

In this Protocol, the following words and expressions shall have the meaning set opposite them:

“Final Approval” means a statement of consent by the ISO Control Center to initiate a scheduled Outage.

“ISO Home Page” means the ISO internet home page at <http://www.caiso.com> or such other internet address as the ISO shall publish from time to time.

OCP 1.2.3 Rules of Interpretation

- (a) Unless the context otherwise requires, if the provisions of this Protocol and the ISO Tariff conflict, the ISO Tariff will prevail to the extent of the inconsistency. The provisions of the ISO Tariff have been summarized or repeated in this Protocol only to aid understanding.
- (b) Unless the context otherwise requires, if the provisions of this Protocol and that of an existing contract conflict, the

scheduling and approval of Outage requests over those which have not been listed.

OCP 4.4.9 Final ISO Approval

On the day an Approved Maintenance Outage is scheduled to commence, a Participating Generator shall obtain Final Approval of the Outage from the ISO Control Center if the scope of work or Outage time has changed with less than seven (7) days prior notification to the ISO Outage Coordination Office. No such Outage shall commence without such Final Approval being obtained from the ISO Control Center, whose decision shall be final.

OCP 4.4.10 Withholding of Final Approval and Rescheduling of Outage

The ISO Control Center shall have the authority to withhold a Final Approval for reasons of System Reliability. The ISO Control Center shall immediately notify the relevant Generator of its intention to withhold the Final Approval. The Generator Maintenance Outage will then be rescheduled pursuant to the Dispatch Protocol.

OCP 5 ISO Controlled Grid Maintenance Scheduling and Approval

OCP 5.1 Schedule Confirmation and Final Approval of Scheduled Outages Required Under the ISO Tariff

Each Participating TO which has scheduled a Maintenance Outage pursuant to OCP 3 must schedule and receive approval of the Outage from the ISO Outage Coordination Office in accordance with OCP 5.4 prior to initiating the Approved Maintenance Outage.

Under no circumstance shall an Operator start any Approved Maintenance Outage without Final Approval from the ISO Control Center being requested and given in accordance with OCP 5.7.

OCP 5.2 Adjacent Control Areas

The ISO will coordinate the scheduling of ISO Controlled Grid facilities and approvals, as necessary, with the operators of adjacent Control Areas.

OCP 5.3 Data Required

All Participating TOs shall submit a formal request to confirm or change an Approved Maintenance Outage with respect to any ISO Controlled Grid facility to the ISO Outage Coordination Office in accordance with OCP 5.3.1 and OCP 5.3.2

